

FINANCIAL BID

Providing ,supplying and fixing in position of copper strip for lighting arrestor and its connection to the existing lighting arrestor set up at Magnetic Observatory, Silchar

Sr No:	Items	Unit	Qty	Rate	Amount
1	Providing and fixing Copper tape 20 mm X 3 mm thk. on parrapet or surface of wall / roof for lighting conductor complete as required (for horizontal run.)for fixing 20 mm x 3 mm tape on paparapet / horizontal surface (with copper / brass saddle, brass screws, PVC fastners etc.)	RMT	177		
2	Providing and fixing Copper tape 20 mm X 3 mm thk. on parrapet or surface of wall / roof for lighting conductor complete as required for (vertical run) for fixing 20 mm x 3 mm tape on paparapet / horizontal surface (with copper / brass saddle, brass screws, PVC fastners etc.)	RMT	40		
3	jointing copper tape with another copper tape , base plate of the finl or any other metalic object by Riveting , nut bolting , soldering sweting soldering and making conection with electrode copper strip	each	50		
4	Providing and fixing testing joint made with strip of 20 mm X 3 mm X 125 mm long with 4 nos of Brass bolts nuts chucks and spring washers ect completd s required.	each	10		
6	Contingent item for joing of lighting arrestor strip with the existing set up of earthing and lighting conductor including replacement of defective parts if any . (This included provisions for only labors for carrying out the work with contingent materials)		lump sum		
Total amount including G.ST . =					

NOTE:

Total amount and rate to be inclusive of all taxes, levis, trasport , GST etc. as may be applicable)

Sign of Contrator :

Date :