

SCHEDULE OF QUANTITIES

Name of work:-Aesthetic improvement by fixing printed Porcelain tiles at compound wall of IIG

Sl.No.	Item Description	Quantity	Unit	RATE	AMOUNT	
17	Providing and fixing Ist quality printed Porceline tiles (thickness to be specified by the manufacturer), of approved make, in background of all colours, shades of any size. Fixing at walls to cover 6 feetx6feet at each panel over neat cement of required thickness and pointing in white cement mixed with pigment of matching shade complete. The subject (theme) to be printed on tiles by digital printing method will be provided by IIG authority. The balance area of each wall panel after fixing 6 feet X 6 feet tiles will be finished with cement based putty and painted with Premium Acrylic Smooth exterior paint with Silicone additives of required shade complete as per direction of IIG authority.	12	Each Panel	31,500	378,000	MR
	Total =				378,000	
	Add GSR @18% on total.				68,040	
	Total =				446,040	

(Rs.Four Lakh Forty Six thousand Forty Only)

Add _____ % Above / _____ % Bellow the Estimated cost

Tendered Cost (including GST) = Rs.

Name, Sign and Seal of the Agency