



## INDIAN INSTITUTE OF GEOMAGNETISM

(An Autonomous Scientific Research Organization under the Department of Science and Technology, Govt. of India)

Quotation No.: IIG/EM/Civil/2024-25/Q/03

Date : 24.05.2024

### NOTICE INVITING QUOTATION

Percentage rate quotations are invited by, IIG for Panvel campus. Eligible and established contractors or Consortium having experience in carrying out similar nature of works for the proposed work of **"Providing and fixing false ceiling with provision of light at Director's P.S room at IIG Panvel Campus."**

The duly filled in quotation to be dropped in Tender Box kept in security cabin, near entrance of IIG, Panvel campus.

The quotations shall be opened on 31.05.2024 at 12:30 hrs. in the presence of contractor / their authorized representatives.

**Name of Work: Providing and fixing false ceiling with provision of light at Director's P.S room at IIG Panvel Campus.**

Sr. No.	Name of Work	Tenure of Work	Quotations Fees (Non Refundable)	Last date and time of receipt of Quotations	Date and time of opening of Quotations
1	Providing and fixing false ceiling with provision of light at Director's P.S room at IIG Panvel Campus.	1 (One) Month	Nil	31.05.2024 11.30 Hrs	31.05.2024 12:30 Hrs

To,

M/s \_\_\_\_\_

### **TERMS AND CONDITIONS**

1. The rates quoted by contractor are all inclusive and nothing extra will be paid.
2. Work shall be executed as per CPWD specification.
3. Applicable taxes shall be deducted from the bill of the contractor.
4. The quoted rates shall be deemed to be inclusive of Taxes / GST or any other tax or Cess etc. and nothing extra shall be paid on any account.
5. The Director, IIG reserves the right to reject any or all the quotations without assigning any reason.
6. The agency should temporarily cover the carpet, furniture and appliances, etc with thick plastic sheet to protect them from splashes, droppings of paint.
7. In case existing furniture / equipment is damaged, cost of the same will be recovered from the agency, if the agency fails to repair/replace the damaged item.

Sd/-

**Registrar**

IIG,

New Panvel, Navi Mumbai.

Copy to:-

Notice Board

**Registrar**

### Original Estimate

N/W	Providing and fixing false ceiling with provision of light at Director's PS room at IIG Panvel
-----	--

SLNo	Description	Qty	Unit	Rate	Amount
<b>1</b>	Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595 mm of approved texture, design and patterns having NRC (Noise Reduction coefficient) of 0.50 (minimum) as per IS 8225:1987, Light reflectance of 85% (minimum). Non combustible as per BS:476 (part-4), fire performance as per BS:476 (part 6 &7), humidity resistance of 100%, thermal conductivity < 0.043 W/m K as per ASTM 518:1991, in true horizontal level suspended on interlocking metal powder coated T-Grid of hot dipped galvanised iron section of 0.40 mm thick on Silhouette profile, rotary stitched double webbed white with 6mm reveal profile (white/black), comprising of main-T runners of size 15x42mm of length 3000 mm, cross - T of size 15x42 mm of length 1200 mm and secondary intermediate cross-T of size 15x42 mm of length 600mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 50 mm long, 8 mm outer diameter M-6 dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 85x25x2 mm. Galvanised iron perimeter wall angle of size 22x19x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450 mm center to center and 40mm long dry wall S.S screws. The work shall be carried out as per specifications, drawing and as per directions of the competent authority.				
<b>1.1</b>	26.23.1 With 15 mm thick integral densified micro edge light weight calcium silicate false ceiling tiles	<b>28</b>	<b>sqm</b>	<b>2630.40</b>	<b>73651</b>
<b>2</b>	Providing, fixing and making connection with nearest switch board 40W 2x2 LED Panel (2 feet x 2 feet Backlit Panel) Cool White Light (6500K). Recessed Panel for False-Ceiling Aluminium Housing for Efficient Performance of make Philips, Wipro Garnet or equivalent make as per direction of competent authority.	<b>4</b>	<b>each</b>	<b>2800</b>	<b>11200</b>
	total =				84,851
	Add Cost Index @15% on DSR items				11,048
	total =				<b>95,899</b>

Add \_\_\_\_\_ % above/ \_\_\_\_\_ % below the estimated cost.

Quotation cost (Including GST):

Name, sign and seal of the agency:

Date: